

CALCUTTA RESCUE
14, Tara Sankar Sarani, Ward No. 05,
Kolkata- 700037.

2ND FLOOR

<u>Sl. No.</u>	<u>Description</u>	<u>Quantity/ Unit</u>	<u>Rate/Unit</u>	<u>Amount</u>
			<u>Rs. P.</u>	<u>Rs. P.</u>
1.	Dismantling of existing Plaster at ceiling and Walls also debris materials shifting all complete	40.00 M ²		
2.	6 mm.th Sand Cement Plaster (1:3) at Ceiling	40.00 M ²		
3.	Two nos new doors Fitting and fixing All complete	2 Nos.		
4.	Tiles fitting for existing Toilet, now at present computer Room floor dado including Cutting polishing etc. All Complete	28.00 M ²		

CALCUTTA RESCUE
14, Tara Sankar Sarani, Ward No. 05,
Kolkata- 700037.

2ND FLOOR

<u>Sl. No.</u>	<u>Description</u>	<u>Quantity/ Unit</u>	<u>Rate/Unit</u>	<u>Amount</u>
			<u>Rs. P.</u>	<u>Rs. P.</u>
5.	75 mm.th. brick work Super Structure (1:4)	3.00 M ²		
6.	Plaster of Putty work For inner side walls, ceiling Including cleaning, etc. All complete	680.00 M ²		
7.	Plastic Paint over a Coat of primer, including Cleaning etc. all complete (both inner side wall and ceiling.	680.00 M ²		

CALCUTTA RESCUE
14, Tara Sankar Sarani, Ward No. 05,
Kolkata- 700037.

2ND FLOOR

<u>Sl. No.</u>	<u>Description</u>	<u>Quantity/ Unit</u>	<u>Rate/Unit</u>	<u>Amount</u>
			<u>Rs. P.</u>	<u>Rs. P.</u>
8.	Painting Work for existing doors and windows over a coat primer	65.00 M ²		
9.	12.5 mm.th cement Concrete (1:2:4) for Existing floor, skirting Including chipping with 6 mm.th. Neat cement finish	30.00 M ²		