

CALCUTTA RESCUE
14, Tara Sankar Sarani, Ward No. 05,
Kolkata- 700037.

GROUND FLOOR

<u>Sl. No.</u>	<u>Description</u>	<u>Quantity/ Unit</u>	<u>Rate/Unit</u>	<u>Amount</u>
			<u>Rs. P.</u>	<u>Rs. P.</u>
1.	Dismantling of existing R.T. Structure Such as Garage, toilet, Room, ect. At back portion of ground Floor	29.00 M ²		
2.	125 th. brick work in cement mortar (1:4) with approved H.B netting in every forth layer	8.00 M ²		
3.	Dismantling of Existing At front portion Urawda Ward installing a collapsible gate.	3.00 M ²		
4.	Installing new Collapsible Gate fitting and fixtures All Complete	1 Nos.		

CALCUTTA RESCUE
14, Tara Sankar Sarani, Ward No. 05,
Kolkata- 700037.

GROUND FLOOR

<u>Sl. No.</u>	<u>Description</u>	<u>Quantity/ Unit</u>	<u>Rate/Unit</u>	<u>Amount</u>
			<u>Rs. P.</u>	<u>Rs. P.</u>
5.	12.5 mm.th. Sand Cement Plastering work (1:5) for Repairing purpose	35.00 M ²		
6.	Outer side wall sand Cement plaster (1:4) Such as , R.C . Lintels, Chajja, walls etc. including Scaffolding making etc.	50.00 M ²		
7.	Back Portion 1 no. door Opening at ground floor and also new window door fitting and fixing all complete.	1 No.		

CALCUTTA RESCUE
14, Tara Sankar Sarani, Ward No. 05,
Kolkata- 700037.

GROUND FLOOR

<u>Sl. No.</u>	<u>Description</u>	<u>Quantity/ Unit</u>	<u>Rate/Unit</u>	<u>Amount</u>
			<u>Rs. P.</u>	<u>Rs. P.</u>
8.	Floor finish (acid Polish my machine) Including Skirting Dado etc. all complete	240.00 M ²		
9.	Plaster Putty work For inner side walls, Ceiling including cleaning, cutting and smoothing ect. All Complete	455.00 M ²		
10.	Weather coat over a Coat of primer (Asian Paint) work including Cleaning etc (Outside Wall only).	220.00 M ²		